Laura Thrasher (660) 785-4326 FAX: (660) 785-7337



McClain Hall 106 100 E Normal Kirksville, MO 63501-4221

## TO: ALL PROSPECTIVE VENDORS

RE: Addendum No. 2 Pershing Building Replacement Gymnasium Floor Project No. SP24-16

Addendum No. 2 is issued to inform vendors that I have received questions that require a response and therefore, an addendum. Please refer to the questions and responses provided.

Please confirm that I have the correct email address for your company. This addendum and subsequent addendums will be sent to all firms who have expressed their interest in submitting a proposal.

Vendors are to acknowledge receipt of Addendum No. 2 in their response.

Please call at 660.785.4326 or send an email at <u>lthrasher@truman.edu</u> if you have any further questions. I look forward to a response from your firm. Thank you.

Sincerely,

Laura K Thrasher

Laura Thrasher Purchasing Buyer

Pershing Building Replacement Gymnasium Floor Project No. SP24-16

## **Question & Response**

- 1. How thick is the wood floor system and does it have a sleeper?
  - a. Action Floor Systems, LLC, Channel Flex Ultra NR 25/32" x 2-1/4" width, 2nd and better maple floor, or University approved equivalent. See attached product section (Attachments A and B)
- 2. Is it adhered directly to the substrate?
  - a. The sports floor system must provide the stability of an anchored floor with the uniform resiliency of a floating system, consisting in general of a vapor barrier, resilient pads, continuous steel channel, steel anchors, wood sub-flooring, maple flooring, sanding, sealers, finishes, game lines and wall base. Flooring system shall have been independently tested and certified to meet or exceed USSL and ISSS standards.
- 3. Has there been any history of moisture issues?
  - a. There has been but the exterior downspouts and connections to the storm lines have been replaced.
- 4. Will the replacement flooring need ramps at the doorways? Assuming the wood system was thicker than the 8mm specification for the replacement flooring.
  - a. That is for the installer to determine. I do not think any ramps will be required as currently the threshold is sloped up to the wood floor.



