

Laura Thrasher
(660) 785-4326
FAX: (660) 785-7337



McClain Hall 106
100 E Normal
Kirksville, MO 63501-4221

TO: ALL PROSPECTIVE VENDORS

RE: Addendum No. 3
Pershing Building Replacement Gymnasium Floor
Project No. SP24-16

Addendum No. 3 is issued to inform vendors that I have received questions that require a response and therefore, an addendum. Please refer to the questions and responses provided.

Please confirm that I have the correct email address for your company. This addendum and subsequent addendums will be sent to all firms who have expressed their interest in submitting a proposal.

Vendors are to acknowledge receipt of Addendum No. 2 in their response.

Please call at 660.785.4326 or send an email at lthrasher@truman.edu if you have any further questions. I look forward to a response from your firm. Thank you.

Sincerely,

A handwritten signature in cursive script that reads 'Laura K. Thrasher'.

Laura Thrasher
Purchasing Buyer

Question & Response

1. Clarification - How thick is the wood floor system and does it have a sleeper? Is it adhered directly to the substrate? Questions 1 and 2 should have been answered as below on Addendum 2.
 - a. Existing wood floor is Action Floor Systems, LLC, Channel Flex Ultra NR 25/32" x 2-1/4" width, 2nd and better maple floor, or University approved equivalent. Following is from the 2013 specs. The sports floor system must provide the stability of an anchored floor with the uniform resiliency of a floating system, consisting in general of a vapor barrier, resilient pads, continuous steel channel, steel anchors, wood sub-flooring, maple flooring, sanding, sealers, finishes, game lines and wall base. Flooring system shall have been independently tested and certified to meet or exceed USSL and ISSS standards. The current flooring is directly adhered to the substrate.
2. Be advised that all access to the small gym in the Pershing Building has stairs.
3. What height of wall base is preferred?
 - a. Truman State University prefers a 6" tall wall base.
4. Is demolition mandatory?
 - a. Per Part II, B. Required Specifications, 2. Demolition in the Request for Proposal
 2. Demolition:
 - a. Demolish and remove existing gymnasium floor and subfloor only to the extent required for new construction.
 - b. Comply with hauling and disposal regulations of authorities having jurisdiction.
 - c. Maintain existing utilities and protect them against damage during demolition.
 - d. Schedule demolition so as not to interfere with Truman's operations.
 - e. Provide temporary barriers to protect against injury and damage to the construction area.